1927

1952

1958

NOTE VACUUM & OXYGEN PIPING

ALL ABOVE PIPING INSTALLED IN EXISTING BUILDING TO BE RUN EXPOSED AT CEILINGS AND WALLS, SAME FOR OUTLETS SEE SCHEDULE.

ALL ABOVE PIPES LOCATED IN NEW ADDITION TO BE CONCEALED IN CEILINGS WALLS SURGERIES ETC AND OUTLETS TO BE RECESSED AS SHOWN IN SCHEDULE

ALL LINES SHOWN ON THIS PLAN ARE A PART OF NEW INSTALLATION FOR COMPLETE VACUUM & OXYGEN SYSTEM THROUGHOUT EXISTING & NEW ADDITION BLDGS.

TYPICAL

THIRD FLOOR PLAN

82-85:1966 addition

FIRST FLOOR PLAN

130-132:1966 addition

GROUND FLOOR PLAN

NOTE: EXISTING BUILDING INDICATED BY DOTTED OUTLINE. EXISTING PARTITIONS ARE DESIGNATED BY SINGLE SOLID LINE.

BASEMENT PLAN

SCALE 1/16" = 1'-0"

ALTERNATES

ALTERNATE No. 1 PLUMBING QUOTE AN ALTERNATE PRICE FOR PROVIDING THE OXYGEN & VACUUM SYSTEM FOR THE NEW ADDITION ONLY & CAP LINES GOING INTO OLD BUILDING.

ALTERNATE No. 2 PLUMBING QUOTE AN ALTERNATE PRICE FOR PROVIDING THE OXYGEN & VACUUM SYSTEM FOR ENTIRE BUILDING (OLD & NEW) AS INDICATED ON THIS PLAN

1927

1952

1958

EXISTING SECOND FLOOR PLAN

SECOND FLOOR PLAN

SCALE 1/16" = 1'-0"

NEW ADDITION

ACCESSORIES

VACUUM BOTTLE & REGULATOR

AREA	QUANTITY
OPERATING NO. 1	
OPERATING NO. 2	
OPERATING NO. 3	
OPERATING NO. 4	
CYSTO ROOM	
RECOVERY ROOM	
TOTAL OF	5

VACUUM BOTTLE WITHOUT REGULATOR

AREA	QUANTITY
OPERATING NO. 1	
OPERATING NO. 2	
OPERATING NO. 3	
OPERATING NO. 4	
RECOVERY ROOM	3
TOTAL OF	7

1 GAL VACUUM BOTTLE & CLEISER

AREA	QUANTITY
OPERATING NO. 1	
OPERATING NO. 2	
OPERATING NO. 3	
OPERATING NO. 4	
CYSTO ROOM	
RECOVERY ROOM	3
TOTAL OF	6

OXYGEN & VACUUM NOTES

ALL INDIVIDUAL BRANCHES TO OXYGEN OUTLETS & BOXES AS INDICATED IN SCHED.

SCHEDULE OF OXYGEN & VACUUM FIXTURES

SYM	SIZE	DESCRIPTION	MOUNTING	QUANTITY
F-1	3/8"	OXYGEN OUTLET SINGLE	EXPOSED	70
F-2	3/8"	OXYGEN OUTLET SINGLE	RECESSED	38
F-3		3/8" OXYGEN & 1/2" VACUUM OUTLET	EXPOSED	1
F-4	3/8"	OXYGEN & VACUUM OUTLETS	RECESSED	4
F-5	1/2"	VACUUM & VACUUM OUTLETS	EXPOSED WITH SLIDE	3
F-6	1/2"	VACUUM & VACUUM OUTLETS	RECESSED WITH SLIDE	1
F-7	3/8"	OXGEN CEILING OUTLET	EXPOSED	3
F-8	3/8"	OXYGEN CEILING OUTLET	RECESSED	1
F-9	3/8"	BOX WITH VALVE	EXPOSED	5
F-10	1/2"	BOX WITH VALVE	EXPOSED	4
F-11	3/8"	BOX WITH VALVE	EXPOSED	5
F-12	3/8"	BOX WITH VALVE	RECESSED	1
F-13	1/2"	BOX WITH VALVE	RECESSED	1
F-14	3/8"	BOX WITH VALVE	RECESSED	3

FLOWMETER PRESSURE COMP.

AREA	QUANTITY
RECOVERY	4
NURSERY	2
OXYGEN TENTS	5
FLOOR USE & OTHERS	12
TOTAL OF	23

HUMIDIFIERS

AREA	QUANTITY
RECOVERY	4
NURSERY	2
FLOOR USE & OTHERS	2
TOTAL OF	8

N

ASSOCIATED ENGINEERS
INCORPORATED
GREENVILLE, SO. CAROLINA

A CHRONIC DISEASE ADDITION TO THE HAYWOOD COUNTY HOSPITAL

WAYNESVILLE, N. C.

6-2-58

P-7
7

A.I.A.